"B" or "Special" List.

12. Hephzibah Devavaram, B.A., care of Dr. E. Devavaram, C. P. S. Hospital, Sivasamudram (Bluff).

Notification No. 2040—C. R. B., dated 6th October 1938.

Kind and Class of Appointments:—Mistresses, Kannada Girls' Middle Schools. Class I.

Unit Office:—The Deputy Director of Public Instruction, Mysore Division.

"B" or "Special" List.

5. Miss Christiana Devados, B.A., Dewan's Road, No. 563, Chamarajpet, Mysore City.

No. 2170—C. R. B., dated 18th October 1938.

Omit "Serial No. 6. H. Radhakrishna Rao, care of Mr. H. Shama Rao, B.A., B.T., Head Master, Sri Lakshmi Narasimha Institute, Fort, Bangalore City" in the 'B' or 'Special' list issued in Notification No. 1265—C. R. B., dated 29th August 1938, for appointment of Assistant Draftsmen and Tracers in the Unit Office of the Superintending Engineer, Irrigation Circle, Krishnaraj Sagar Works, Mysore.

By Order,
K. THIPPERUDRIAH,
Secretary,
Central Recruitment Board.

ENGINEERING DEPARTMENT.

BUILDINGS DIVISION, BANGALORE.

Notification dated 15—17th October 1938.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Buildings Division, up to 2 P.M., on Monday the 7th November 1938, for extending the class rooms of the Boys' Middle School at Chamarajpet, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the class rooms of the Boys' Middle School at Chamrajpet, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for extending the Class Rooms of the Boys' Middle School at Chamrajpet, Bangalore City.

Sl. No.	Item of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	(*a*) Dismantling Compound wall	C.ft.	0 0 4	391	
	(*b*) Removing stone foundations and iron gate shutters and stocking	L. S.	..	..	
	(*c*) Removing couples and stacking	Each	1 0 0	2	
	(*d*) Removing eve boards and ridge tiles, etc. ..	L. S.	..	..	
2	Earthwork excavation	C.yd.	0 3 6	112	
3	Granite jelly concrete in lime mortar	C.ft.	0 3 6	857	
4	Burnt size stone in lime mortar with bond stones 6 ft. apart	C.ft.	0 4 6	1,627	
5	Providing burnt stone pillars 5″ to 6″ one line dressed and fixed in mortar for verandah walls.	S.ft.	0 5 0	82	
6	Burnt stone pillars 5″ thick, two lines dressed on all sides cutting grooves for Bressummers for verandah 9½ ft. high	Each	7 8 0	10	
7	Burnt brick in clay for superstructure	C.ft.	0 3 3	2,997	
8	Moulding perforated ventilators, in brick in mortar as per existing design	S.ft.	1 8 0	93	
9	Teakwood wrought and put up including wood-oiling	C.ft.	4 8 0	154	
10	Fixing old couples with necessary bolts and nuts ..	Each	2 0 0	2	
11	Roofing first class Mangalore tiles over teakwood reepers of 2″×1″ with nails, etc.	Sqr.	20 0 0	26·40	
12	Fixing ridge tiles in mortar and cement pointing ..	R.ft.	0 7 0	88	
13	Preparing and fixing eve boards 9″×¾″ and painting	R.ft.	0 7 0	88	
14	Fixing old eve boards with painting	R.ft.	0 2 0	60	
15	Lime mortar plastering including two coats of white washing	Sqr.	3 0 0	54·73	
16	Fixing expanded metal ¾″ mesh with teakwood frame 2½″×3½″ with door half pannelled and half expanded metal including iron fittings ..	Sqr.	0 10 0	456	
17	Painting for expanded metal, two coats of approved paint	Sq.	3 8 0	2·00	
18	Pebble plastering in lime mortar including colour washing as per existing design including ornamental band patties, etc., complete	Sqr.	4 0 0	9·89	
19	Coping for compound wall with burnt brick in mortar 1½′×9″ and plastering, etc., complete ..	R.ft.	0 4 6	57	
20	Flooring with cement concrete, 2″ thick over 3″ lime mortar concrete with red ochre mixed cement plastering and cut lines, etc., complete ..	Sqr.	23 0 0	12·00	
21	Ornamental works during execution	L. S.	..	..	
22	Flooring with 1½″ thick Cuddapah slabs over 3″ lime mortar concrete and cement pointing ..	Sqr.	20 0 0	3·50	
23	Mortar band for roof in burnt brick in lime mortar and plastering 9″×4½″	R.ft.	0 3 0	56	
24	Cement pointing to basement with cut lines ..	Sqr.	3 0 0	3·24	
25	Fixing the old gate with available pivots, etc., complete	Sqr.	0 2 0	51	

Notification dated 17th October 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2 P.M. on 8th November 1938, for constructing the proposed additions to the office of the Director, Geological Department, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 260 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the proposed additions to the office of the Director, Geological Department, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing the proposed additions to the Office of the Director, Geological Department.

Sl. No.	Particulars	Unit	Rate	Contents	Cost
			Rs. a. p.		
1	Earthwork excavation and filling	C.yd.	0 3 0	75	
2	Lime mortar concrete	C.ft.	0 3 6	525	
3	Stone in mud, etc.	,,	0 3 6	1,554	
4	B. S. slabs 6" thick, one line dressed and fixed ..	Sq. ft.	0 5 0	967	
5	Mysore teakwood doors complete pannelled with iron fittings, etc., complete	,,	1 6 0	114	
6	Mysore teakwood windows complete pannelled with iron fittings, etc., complete	,,	1 8 0	243	
7	Stone pillars 9" square, 8' high, two line dressed and fixed with base and capital	No.	20 0 0	13	
8	Burnt brick in mud	C.ft.	0 3 6	2,817	
9	Burnt brick in mortar	,,	0 4 6	1,052	
10	Mysore teakwood wrought and put up	,,	4 8 0	61·45	
11	Roofing with R.C.C. 6" thick (1 : 2 : 4) for a clear span of 14' to take a load of 1½ Cwt. per sq. ft. 3" surki concrete, two layers of flat tiles and plastering	Sqr.	80 0 0	15·84	
12	Valley plank, etc., fixing	Sq. ft.	0 9 0	84	
13	Zinc sheets for valley including fixing, etc. ..	,,	0 5 0	84	
14	First class Mangalore tiled roof on T.W. rafters with wood-oiling	Sqr.	20 0 0	10·15	
15	Mortar band, etc., complete	R.ft.	0 3 0	162	
16	Ornamental cornice complete 9"×9"	,,	1 0 0	234	
17	Parapet wall complete	,,	1 8 0	234	
18	Lime mortar plastering	Sqr.	5 4 0	57·46	
19	White or colour washing	,,	0 4 0	57·46	
20	Cement concrete (1½") flooring on 3" lime concrete and half inch red cement plaster, etc., complete.	,,	18 0 0	17·84	
21	Cement pointing	,,	2 8 0	4·19	
22	Painting to doors and windows with approved paint green	,,	4 0 0	8·45	
23	Ornamental eve board	R.ft.	0 10 0	110	

B. R. GARUDACHAR,
Executive Engineer.